



CONTRACTING AUTHORITY'S CLARIFICATIONS No. 3

Project title:

Electrical equipment for the reaction in emergency situations

Publication reference: EuropeAid/137100/DH/SUP/RS

No.	Question	Answer
1.	Please clarify how the risk of loss and damage to the goods provided for in Clause 12.1 (a) General Conditions and the DDP delivery term in Clause 16 General Conditions go together? Pursuant to the latter, risk passes at the time of delivery and not at the end of the warranty period as provided for in said Clause 16.	As per Article 12.1 of Special Conditions, "All equipment supplied shall be covered by "all risk" insurance in Euros against any form of loss or damage from unloading, warehouse, throughout the construction period until final commissioning and signing by the Supervising Engineer for the works contract of Provisional Acceptance Certificate. The goods shall be insured acting the Contracting Authority as insurance's beneficiary and owner of the goods."
2.	Please clarify whether in accordance with Clause 41 General Conditions, Serbian or Belgian law applies?	This contract shall be governed by the European Union law supplemented as appropriate by Belgian law.
3.	3. The Part B_Lot 1_Annex II+III TS + TO/ Lot 1_Tech spec / S2_L1_01 TS_MSS 110-35.doc file contains in specification 35kV Voltage Transformers for 35kV switchgears but at drawings the 35kV VTs have not been signed/mentioned. Please clarify the need.	<p>In the Part B_Lot 1_Annex II+III TS + TO/ Lot 1_Tech spec / S2_L1_01 TS_MSS 110-35.doc file on page 33 instead of "35 kV feeder bays shall be equipped with a switch, three position disconnectors, current transformers and a voltage transformer" the following wording should stand: "35 kV feeder bays shall be equipped with circuit breakers, three position disconnectors, current transformers, cable (ring type) current transformers, surge arresters and capacitive voltage indicators". This should as such be designated on the Tender drawing 01_110-35 kVA_SLD.</p> <p>On the same page (33) of the same document instead of "35 kV transformer and measuring bay shall be equipped with a switch, three position disconnector, current transformer and a voltage transformer" the following wording should stand: "35 kV transformer and measuring bay shall be</p>

No.	Question	Answer
		equipped with a circuit breaker, three position disconnecter, current transformer, voltage transformer and two capacitive voltage indicators - one as designated in the Tender drawing 01_110-35 kVA_SLD and the other in the bus-bars compartment of the bay which should indicate the presence of voltage on the busbars”.
4.	<p>In the Contract Notice of the above mentioned tender;</p> <p>16 Selection Criteria: 3 a) “For Lot 1..... under at least 1 contract with a budget of at least 500,000 Euro... For Lot 2..... under at least 2 contracts with a budget of at least 300,000 Euro.... For Lot 3.... under at least 1 contract with a budget of at least 500,000 Euro...”</p> <p>However in the Evaluation Grids for different lots of the same tender;</p> <p>Lot 1 Detailed Technical Evaluation Grid 4.1 ... under at least 1 contract with a budget of at least EUR 1,000,000... Lot 2 Detailed Technical Evaluation Grid 4.1 ... under at least 2 contracts with a budget of at least EUR 500,000 Lot 3 Detailed Technical Evaluation Grid 4.1 ... at least one similar projects with a budget of at least 1,000,000 EUR</p> <p>So there is a difference can you please keep the limits in the contract notice for higher participation?</p>	<p>The Selection criteria are as published in the Contract Notice:</p> <p>3 a) “For Lot 1..... under at least 1 contract with a budget of at least 500,000 Euro... For Lot 2..... under at least 2 contracts with a budget of at least 300,000 Euro.... For Lot 3.... under at least 1 contract with a budget of at least 500,000 Euro...”</p>
5.	<p>In the Contract Notice of the above mentioned tender;</p> <p>Special Conditions for Lot 3, Article 19 states the implementation period is 728 days</p> <p>However in the Contract Execution Plan for Lot 3 states that; 104 weeks.</p> <p>Could you please clarify which period is correct for implementation for Lot 3?</p>	<p>Both information are correct, given that 104 weeks is exactly 728 days.</p>